

Instructions for Wall Mount Tree Assembly

1) Mount Main Panel securely in desired location. **Installation must be capable of supporting the weight of this unit with all shelves fully loaded.** Mounting holes in panel are provided at 16" on center, matching typical wall stud spacing.

2) Insert shelves in desired locations. Note that shelves can be installed flat or tilted at a 20° angle. Use the small holes adjacent to the mounting slots as reference points to help align the shelves across the unit.

